

Bid Addendum Report

Baragung Muktikshetra Rural Municipality

Baragung Muktikshetra Rural Municipality
Mustang
Mustang
Nepal

Addendum No: 1

Published On: 12-04-2020 00:00

Invitation No: 03/VMRM/NCB/W/076/77

Dated On: 13-03-2020 00:00

Following changes are made in the bid document

Chapter: General Information

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	Not Provided in Bid Document	2020-04-12 00:00:00
2	Bid Submission DeadLine	2020-04-12 12:00:00	2020-04-22 12:00:00
3	Bid Opening Date	2020-04-12 14:00:00	2020-04-22 14:00:00
4	Works Start Date	23-04-2020	30-04-2020

Chapter: Bill of Quantities

1 Provisional Sum						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)	
1	Project description board at construction site- making, fixing all complete work as per instruction	Job	1	5000	5000	
2	Third party insurance as per condition of the contract	PS	1	17114	17114	
3	Insurance of the work as per condition of the contract.	ps	1	17114	17114	
4	Insurance against accident to work man as per condition of the contract	ps	1	17114	17114	
5	Lab Test	Job	1	8557	8557	
2 Construction work						
2.1 River Training Work						
2.1.1 Civil Work						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Earthwork in excavation in dry foundation excavation in hard gravel mixed soils (dia of gravel <10cm) with disposal up to 10 m lead and 1.5 m lift.	cum	416.16			
2	150 mm Thick Dry Stone Soling Work.	cum	36.72			
3	Concreting of foundations, vertical faces, Walls (Cement Concrete) incl. supply of materials and haulage distance up to 30 m.PCC 1:2:4	cum	24.48			
4	Concreting works of superstructures, deck slab, beams including supply of materials and haulage upto 30m 1:1.5:3 RCC.	cum	202.64			
5	Making wooden forms including supply and selection of materials fixing nailing according to drawings, placing separators, dismantling forms & hauling up to 30m distance.	sqm	819.51			
6	Reinforcement for RCC works including supply of materials, cutting, bending placing in position and binding of rod all complete.	kg	12995.99			

Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
7	Earthwork in back filling in foundation	cum	208.08			